







Length 长度(mm)	Width 宽度(mm)	Height 高度(mm)	Pay Cat. 付款等级	Line 行号	Qty. 数量	Mark 构件号	Sub Mark 次构件号	Description 描述尺寸	Material 材质	Length 长度(mm)	Finish 油漆	ABM 材料订单号	Weight 重量(kg)	REMARK 备注
1800	462	290		1	1	CO007		Column						
				2	1		CO007	HW250x250x14	Q355B	1784	G		128.13	
				3	1		p47	PL16x290	Q355B	290	G		10.58	
				4	1		p100	PL10x12.7	Q355B	318	G		6.07	
				5	1		p101	PL10x115.5	Q355B	220	G		1.92	
				6	2		p124	PL12x115.5	Q355B	220	G		4.33	
				7	1		p125	PL12x115.5	Q355B	220	G		2.30	
				8	1		p126	PL12x110	Q355B	116	G		1.10	
				9	1		p127	PL12x100	Q355B	116	G		1.00	
												TOTAL	155.41	

ASSEMBLY BOLT LIST (FOR 1 ASSEMBLY)					
Dia.	Grade	Pay Code	Length	No.	Site/Shop
20	A325M	G	C1	70	4
20	A325M-DTI	G	C1	75	8

(Mechanical galvanized only for DTI washer)



REV	DATE	REVISION	BY	CHKD	APVD	APVD
00	23JUN25	ISSUE FOR FABRICATION	WF	WW	YF	YF
1		REVISION	BY	CHKD	APVD	APVD

RETURN TO VENDOR RESPOND BY

☐ 1 REVISE AND RESUBMIT

☐ 2 TO BE ISSUED AS FINAL PROVIDED COMMENTS ARE INCORPORATED

☐ 3 NOT COMMENT - FINAL ISSUE

☐ 4 FOR INFORMATION ONLY

North Field South Project Onshore LNG Facilities



COMPANY CONTRACT NO.:	LTCINF5649821	CONTRACTOR JOB NO.:	N/A
P.O.:	215777C008-00000-PO-1800-20301-NFS620		
REQUISITION NO.:	NFS_EPC-TECC-ST-REQ-20301		
EQUIPMENT NAME:	PACKAGE - III- STEEL STRUCTURES (Offsite Area)		
TAG NO.:	361-RC3210-S-01		
VENDOR NAME:	UNITED STEEL STRUCTURES LTD.		
DOCUMENT CLASS:	3		
VENDOR DOCUMENT NO.:	ST20301-02048		

TITLE	INLET AREA	SCALE	1:10	PROJECT NO.	LTCINF5649821
STEEL STRUCTURE DRAWING		PROJECT DOCUMENT NO.	5496_21-ST20301-02045	SHEET No.	1
361-RC3210-S-01-CO007		SIZE	A3	REVISION	00

1. ACCUMULATIVE DIMENSIONS ARE TAKEN FROM THE "TOP" LINE. 累积尺寸系从顶部线 "TOP" 开始计算。
2. ALL DIMENSIONS SHALL HAVE A TOLERANCE OF ±1mm UNLESS OTHERWISE SPECIFIED. 除非另有规定, 所有尺寸公差均为 ±1mm。
3. ALL DIMENSIONS THIS SHEET TO BE PROVIDED DIMENSIONS SHALL BE PROVIDED DIMENSIONS. 此图上的所有尺寸均为提供尺寸。
4. ASSEMBLY MARK TO BE STAMPED ON THE FACE WHERE INDICATED THEREIN. 构件号打钢印, 标记在图上。
5. "P" INDICATES THE TOUCH FACE OF MEMBERS, SHIP ALIEN SPOT THEREIN. "P" 为接触面, 2.7 为船体表面。
6. ALL THE DIAMETER OF SCALLOP IS 25mm UNLESS OTHERWISE SPECIFIED. 除非另有规定, 所有圆孔直径均为 25mm。
7. ALL WELDS SHALL BE CONTINUOUS, UNLESS OTHERWISE SPECIFIED. 除非另有规定, 所有焊缝均为连续焊缝。
8. REAL WELDS OF 3MM FILLET WELD SHALL BE PROVIDED IN WELDED CONNECTIONS. 焊缝节点处应提供 3mm 角焊缝。
9. TOPWATER BOLTS SHALL BE RED COATED TO CORROSION FROM THE PERMANENT MOIST. 顶部螺栓应涂红漆, 以防永久锈蚀。

1	B/1-2/QNHD +19.000
QTY	MEMBERS LOCATION